

Document 00910

**ADDENDUM NO. Three**

Date of Addendum: 31 Aug 2005

PROJECT NAME: Jesse H. Jones Central Library Renovation-  
Carnegie Regional Branch Library Renovation-  
Library Resource Center Renovation-

PROJECT NO: E-0011-01-3  
E-0142-01-3  
E-0076-01-3

PROPOSAL SUBMITTAL DATE: **Revised to: September 8, 2005**

08.31.05



FROM: City of Houston, Building Services Department  
900 Bagby, 2<sup>nd</sup> Floor  
Houston, Texas 77002  
Attn: Jack Welker, Project Manager

TO: Prospective Proposers

This Addendum forms a part of the Request For Competitive Sealed Proposals and will be incorporated into the Contract documents, as applicable. Insofar as the original Project Manual and Drawings are inconsistent, this Addendum governs.

**CHANGE IN PROPOSAL SUBMITTAL DATE**

The Proposal Submittal Date for this Project has been changed from September 1, 2005 to September 8, 2005. The time and place for the Submittal Proposal remains the same.

This Addendum uses the change page method: remove and replace or add pages, or Drawing sheets, as directed in the change instructions below. Reissued Drawing Sheets show the Addendum number above the title block and changes in the Drawing are typically noted by a revision mark and enclosed in a revision cloud.

**CHANGES TO PROJECT MANUAL & DRAWINGS**

**CLARIFICATIONS**

- Item # 1. Note the following revisions, per responses to FF&E vendor and manufacturer Requests for Information (RFI):
- 1.) XF-3 (Add to Spec: Existing 5 Drawer Lateral File 36" wide),
  - 2.) XD-1 (Add to Spec: Existing Desk, size varies)

00910-1

08-31-2005

- 3.) XCR-1 (Add to Spec: Existing Credenza, size varies)
- 4.) XT-1 (Add to Spec: Existing Marble top Tables),
- 5.) XT-8 in the reception area of 448 (Add to Spec: Existing coffee table, Granite top)
- (Add Spec for X-SH-2 to read; Existing open Bookcase, size varies.)
- 6.) T-40 (Located in private offices of LRC, QTY of 2 total, not on plan)
- 7.) A-12 (QTY of One in Director's office)
- 8.) T-30 Table Configuration (Located in Children's, Room C123C, Qty of 3 total, not labeled on plan)
- 9.) S-30 (Delete from Spec. Not Used)
- 10.) T-13, T-13A, T-13D
  - Laminate Specification should read: Mfg: Arpa
  - Pattern: Creativita Seventies
  - Distributed by Design Products 1-800-994-6899

**Item # 2.** The following information is in regard to the new waterproofing rigid insulation thickness in the Plaza Level of the Jesse Jones Library facility.


- 1. The new insulation thickness will vary with location in the revised Plaza Deck system. The new insulation thickness is affected by the slope of the existing cast-in-place concrete deck system, the thickness of the existing paver and grout setting bed, and the contour of the new concrete topping slab to be installed above the insulation.
- 2. The thickness of the existing paver and grout setting bed varies with location. Excavations into the existing pavers and setting bed in the Plaza level revealed the following criteria that shall be maintained with the new waterproofing and topping:
  - A. The existing paver and setting bed total thickness at the base of the exterior wall of the Jesse Jones Building (Southeast corner) is approximately 7 5/8-inch.
  - B. The existing paver and setting bed total thickness at a location approximately 24 feet west of the south trench drain is approx. 6 1/4-inch.
  - C. The existing paver and setting bed total thickness at the south trench drain is approximately 4-inches.

**Item # 3.** Carnegie Library carpet will match the carpet specification for the LRC (Library Resource Center) carpet: Oceana, 4502, Amphitrite or "Equal".

**Item # 4.** All new data cabling in the Project, for all buildings, shall be Category 6 cabling.

**Item # 5.** The black/white triangles on all the "TC" sheets are intended to denote combined voice/data outlets.

**END OF ADDENDUM NO. Three**

  
\_\_\_\_\_  
William D. Reesby, P.E. Assistant Director  
Design & Construction Division  
Building Services Department  
DATE 31 Aug 2005

**END OF DOCUMENT**