

AGENDA ITEM: IVd

HPO File No. 101104

SITE NAME:

SITE LOCATION: 1240 Ashland Street – Houston Heights Historic District West

Owner: Kristine Vu

Applicant: Miguel Talamantes

Time Frame	Date Accepted	90-day Waiver
	November-1-2010	N/A

SITE INFORMATION: Lot 19, Block 185, Houston Heights, Houston, Harris County Texas. The site includes a historic one story wood framed house and detached one story garage.

TYPE OF APPROVAL REQUESTED:

The applicant seeks approval of a Certificate of Appropriateness for the following work:

- Construct a new 815 square foot addition to the rear of the existing 1,014 sq. ft one story wood frame house; The proposed one story addition will be set back approximately 32'-0" from the front façade of the existing building; Addition will extend 7'-8" beyond north side wall of existing house and will extend an additional 26'-0" towards the rear property line; The proposed addition will be covered by an intersecting hipped roof with an overall height to new roof ridge of 24'-0" which is 2'-0" taller than existing; Addition will be clad in horizontal lap wood siding to match existing;
- East Elevation (Front - Facing Ashland Street); Proposed addition will not feature any doors or windows;
- South Elevation (Facing Side Property Line); Proposed addition will feature a pair of windows with 1/1 glass lites to match other elevations; The rear portion of the addition will feature a small inset porch which will be more fully described in the west (rear) elevation;
- North Elevation (Facing Side Property Line): The proposed addition will feature three double hung sash windows with 1/1 glass lites to match other elevations;
- West Elevation (Facing Rear Property Line): Addition will feature a partial width inset porch which will feature a perimeter hand rail 42" in height; The porch roof will be supported by 6"x6" square columns; Inset porch area will feature a door with solid lower panels and glass upper half;

HISTORY AND SIGNIFICANCE:

At the time of the Houston Heights Historic District West survey, the hipped gable front cottage, constructed circa 1915, was classified on the inventory as "Contributing".

The property is contained within the boundary of the Houston Heights Historic District. The Historic District is contained within the boundaries of Houston Heights, which was designated as a Multiple Resource Area (MRA) on June 22, 1983 by the National Park Service. Houston Heights was designated as a MRA because it was at one time an independent municipality of less than 50,000 inhabitants (1896-1918), a requirement of the designation, and the area also contains a large number of buildings that have been individually listed in the National Register of Historic Places, another requirement. On April 10, 1991 in conjunction with the Houston Heights Centennial Celebration that year, Houston City Council designated the entire Houston Heights Subdivision as Houston Heights Historic District of the City of Houston (Resolution No. 91-15). The resolution proclaimed Houston Heights as "one of the first planned communities in the State of Texas ... the largest intact historic district in the city tangible evidence of Houston's architectural and historical legacy an area with great potential for enhancement and revitalization as a point of interest in the city." While that designation granted no powers or conferred no rights or privileges associated with the designation, it was the second of such resolutions passed by City Council to recognize neighborhoods in Houston for their historical and architectural

CERTIFICATE OF APPROPRIATENESS

AGENDA ITEM: IVd

HPO File No. 101104

SITE NAME:

SITE LOCATION: 1240 Ashland Street – Houston Heights Historic District West

significance to the city. The resolution designating Houston Heights had also been recommended to City Council by the Houston Archaeological and Historical Commission (HAHC) at the request of the Houston Heights Association (HHA). The action taken by City Council was also warranted as Houston Heights had been honored previously in 1988 when the Houston Heights Urban Main Street Project on West 19th Street was established by the Texas Historical Commission and the National Trust for Historic Preservation. The program successfully achieved economic development and at the same time preserved the historic buildings which enhanced the success and made it unique. The Texas Historical Commission approved a Recorded Texas Historical Landmark (Subject Marker) for Houston Heights which was dedicated during the Centennial Celebration in 1991. Many other sites and buildings in Houston Heights have been designated as Recorded Texas Historical Landmarks as well. After the passage of the city’s Historic Preservation Ordinance in 1995 by City Council, many buildings have been designated also as City of Houston Landmarks and Protected Landmarks.

Houston Heights was so well planned from its inception by the Omaha and South Texas Land Company in 1891, and as the result, it became very attractive to investors, and Houston Heights grew rapidly and eventually was incorporated as a city in 1896. It flourished as a distinct municipality until 1918 when the residents, by vote, agreed to be annexed to the City of Houston. The reason that the citizens of Houston Heights voted for the annexation to Houston was primarily to guarantee a broader tax base with which to support their public schools. Houston Heights voted "dry" in 1912, guaranteeing that alcohol may not be sold – an extremely unique ordinance adopted by Houston Heights and continuously enforced by the City of Houston. Houston Heights grew rapidly in the 20th century, but continued to maintain its unique identity, which was reflected in its original planning. Today the area still maintains the feeling of a distinctive, self contained “small town” with its predominantly small 19th century, one-story cottages and larger, two-story Victorian-era homes, and numerous early 20th century bungalow style buildings. It also boasts a thriving business district on 19th Street (now predominantly antique shops, retail and restaurants) and a large industrial district west of the business section. The neighborhood also contains the original city hall of Houston Heights (also the fire station and jail). Also located there are a number of historic churches, theatres, corner stores, private and public parks, fraternal halls and schools.

Sec. 33-241. Same-Alteration, rehabilitation, restoration and construction.

(a) The HAHC shall issue a certificate of appropriateness for the alteration, rehabilitation, restoration or construction of an exterior feature of (I) any landmark, (II) any building, structure or object in an historic district, or (III) any building, structure or object that is part of an archaeological site, upon finding that the application satisfies the following criteria, as applicable:

S D NA S - satisfies D - does not satisfy NA - not applicable

- (1) The proposed activity must retain and preserve the historical character of the property;
- (2) The proposed activity must contribute to the continued availability of the property for a contemporary use;
- (3) The proposed activity must recognize the building, structure, object or site as a product of its own time and avoid alterations that seek to create an earlier or later appearance;
- (4) The proposed activity must preserve the distinguishing qualities or character of the building, structure, object or site and its environment;
- (5) The proposed activity must maintain or replicate distinctive stylistic exterior features or examples of skilled craftsmanship that characterize the building, structure, object or site;
- (6) New materials to be used for any exterior feature must be compatible with the materials being replaced in composition, design, texture and other visual qualities;
- (7) The proposed replacement of missing exterior features, if any, should be based on an accurate duplication of features, substantiated by available historical, physical or pictorial evidence, where that evidence is

CERTIFICATE OF APPROPRIATENESS

AGENDA ITEM: IVd

HPO File No. 101104

SITE NAME:

SITE LOCATION: 1240 Ashland Street – Houston Heights Historic District West

available, rather than on conjectural designs or the availability of different architectural elements from other structures;

- (8) Proposed additions or alterations must be done in a manner that, if removed in the future, would leave unimpaired the essential form and integrity of the building, structure, object or site;
- (9) The proposed design for alterations or construction must not destroy significant historical, architectural or cultural material and must be compatible with the size, scale, material and character of the property and the area in which it is located;
- (10) The setback of any proposed construction or alteration must be compatible with existing setbacks along the blockface and facing blockface(s); and
- (11) The proposed activity will comply with any applicable deed restrictions.

STAFF RECOMMENDATION: Approval of the certificate of appropriateness as requested by the applicant.

CERTIFICATE OF APPROPRIATENESS

AGENDA ITEM: IVd

HPO File No. 101104

SITE NAME:

SITE LOCATION: 1240 Ashland Street – Houston Heights Historic District West

**Site Location Map
Not to Scale**



CERTIFICATE OF APPROPRIATENESS

SITE NAME:

SITE LOCATION: 1240 Ashland Street – Houston Heights Historic District West

**Photo of House
Showing Current Condition**




CERTIFICATE OF APPROPRIATENESS

SITE NAME:

SITE LOCATION: 1240 Ashland Street – Houston Heights Historic District West

**Site Plan
Showing Proposed Rear Addition
Not t Scale**



CERTIFICATE OF APPROPRIATENESS

AGENDA ITEM: IVd

HPO File No. 101104

SITE NAME:

SITE LOCATION: 1240 Ashland Street – Houston Heights Historic District West

**Front (East) Elevation
Facing Ashland
Not to Scale**



CERTIFICATE OF APPROPRIATENESS


AGENDA ITEM: IVd

HPO File No. 101104

SITE NAME:

SITE LOCATION: 1240 Ashland Street – Houston Heights Historic District West

**Side (South) Elevation
Facing Side Property Line
Not to Scale**



CERTIFICATE OF APPROPRIATENESS


AGENDA ITEM: IVd

HPO File No. 101104

SITE NAME:

SITE LOCATION: 1240 Ashland Street – Houston Heights Historic District West

**Side (North) Elevation
Facing Side Property Line
Not to Scale**



CERTIFICATE OF APPROPRIATENESS

SITE NAME:

SITE LOCATION: 1240 Ashland Street – Houston Heights Historic District West

**West Elevation
Facing Rear Property Line
Not to Scale**



CERTIFICATE OF APPROPRIATENESS